

Installation and Energization of the World's First EHV Rapid Response Multi-Voltage Transformer Lease (#314)

Eduardo Gomez Hennig, Scott Gray, David Calitz & Ewald Schweiger








Multi-Voltage Resilience GSU for rapid deployment

Mobile




Compact and lightweight design

Versatile



Covering different ratings

Rapid Installation



Plug and Play connections and bushings





Multi-Voltage Resilience GSU Characteristics

First glance - 345 kV GSU in the test bay

- → Flexible
- → Quick Deployment

Technical data

Three units 83.3 MVA – single-phase – 60 Hz (250MVA bank) Possible operating voltages (@ three phase rating):

	Vector Group	D	D	Υ	D	Υ	D	Υ	D	Υ	D	Υ
police	LV Voltage [kV]	34.5	20	34.6	18	31.2	16	27.7	14	24.3	12	20.8
HV Voltage [kV]	400*)	•	- /	-	-	-/	-	-	-	-		-
	345	-	•	•	•	•	•	•		•	•	•
	230	-	•	•	•	•	•	•	•	•	•	•
	138	-	•	•	•	•	•	•	•	•	•	•
	115	-	•	•	•	•	•	•	•	•	•	•

Tertiary 13.6kV *)400kV via adapter and BIL 900kV

- Switching links utilized to change between operating voltages
- Noise level 75 dB(A)
- KDAF Ester Fluid Synthetic Ester MIDEL 7131
- Plug-in bushings and LV cable connections (60m ~196ft)

Low transport weights:

- Fully assembled and oil filled: ~214,000 lbs., 97 t
- Transport weight (transformer) w/o oil: ~114,600 lbs., 52 t
- Unit assembly without oil: ~135,000 lbs., 62 t
- Oil: 9,740 gal, 78,882 lbs., 35.8 t





Installation, configuring voltages, processing, filling and testing

- Installation of 3 single phase units, conservators and coolers
- Configuring operating voltages
- Installation of all accessories and piping
- Vacuum processing and oil filling of transformers
- Bushing testing and installation
- Testing of single-phase transformers
- Arrester testing and installation
- Testing all accessories, alarms, trip contacts, etc.
- Installation and testing of isophase modifications
- Installation and testing of station service transformers
- Connecting and testing of main control cabinet
- → Successful commissioning







Multi-Voltage Resilience GSU Characteristics

- Need lots of manpower! 6.4 Lbs./ft (9.5 kg/m)
- 36 x 200 ft (~60 m) cables installed
- Total installed cable length of roughly 7200 ft (2195 m)
- Maintained 3 ft (~1 m) spacing between cable bundles
- Installed control cables between transformers and main control cabinet
- Cables tied down onto wood mats/timbers
- Testing unit as a three-phase bank to verify ratio and phase relation
- Connecting the main HV jumpers
- Installation of isophase busbar links
- Remove all tools, materials and debris
- Check all switches for proper operation and set to positions for normal operation
- Clean up laydown area and prep for long term storage
- Final inspection/walkdown
- → Ready for energization!







Thank You! - Questions?





